# Suitable over concrete or wood subfloors

Delta IIC 24

IIC 71 IIC 60

STC 66 STC 54



#### For Use Under

- Laminate
- Engineered Wood
- · Solid Wood

#### **Installation Methods**

- Floating
- Double Glue Down







EXCELLENT SOUND ABSORPTION



EXCLUSIVE MOISTURE PROTECTION



PPROVED R INFLOOR



ADDING SULATION





# INSTALLATION METHODS

#### **FLOATING FLOORS**

- 1. Roll out underlayment vapor barrier side up and butt seams together
- 2. Tape seams with provided lip & tape, or moisture barrier seam tape
- 3. Click & lock floating floors over the top according to manufacturer

#### **DOUBLE GLUED DOWN FLOORS**

- Roll out underlayment with the vapor barrier side up and butt seams together
- With a utility knife cut off the overhanging lip/flap before applying adhesive
- Adhere to subfloor using recommended flooring manufacturer's adhesive and recommended trowel size and install method
- 4. Roll over the underlayment with a 75 or 100 pound roller
- Adhere flooring over the top using manufacturer's recommended adhesive and trowel size

#### **NAIL AND STAPLE FLOORS**

Nail down methods are no longer approved for QuietWalk Plus after 07/01/2024.

\*ENSURE TO READ THE COMPLETE INSTALLATION INSTRUCTIONS BEFORE INSTALLATION

# **ENVIRONMENTAL ATTRIBUTES**

- QuietWalk Plus is GREENGUARD and GREENGUARD Gold certified for low chemical emissions (UL2818) and conforms to Collaborative for High Performance Schools (CHPS) – CA Section 01350
- QuietWalk Plus contains 94% post industrial/pre-consumer fibers.
- QuietWalk Plus is LEED ™ compliant and will contribute to:
- -MRc4.1-4.2 recycled content credit
- -EQ 4.3 low-emitting materials credit

# **LIMITATIONS**

QuietWalk Plus is not suitable for use as underlayment for:

- Ceramic tile Sheet-vinyl VCT
- Installations over concrete in high moisture areas (vapor emission rate above 7lbs/1000 sq ft/ 24 hrs as measured with a calcium chloride test kit) will require additional protection such as a concrete sealant or polyethylene vapor barrier.

# **APPROVED SUBSTRATES**

- Dry, completely cured concrete (at least 28 days old)
- · Concrete and masonry blocks
- · Cement backer units (CBU)
- Cementitious screeds, leveling coats and mortar beds
- Waterproofing and crack-isolation membranes
- Wood, plywood, or OSB subfloors that meet NWFA Subfloor Guidelines and Specifications, and meet applicable building codes
- Cement terrazzo floors

#### **PACKAGING**

3' x 33.4' (100 sq ft) do-it-yourself size rolls
Rolls per pallet: 30 Weight per pallet: 400lbs
Pallets per truck: 64 Rolls per truck: 1920
6' x 60' (360 sq ft) contractor sized rolls available.

# Moisture Absoption Properties

Moisture Absorption Approx. 650% by weight

Moisture Statement. QuietWalk Plus will absorb and allow dispersion throughout the product of water moisture in accumulations not exceeding one gallon per 24 hrs per 300 square feet of product and/or allowed to continue to accumulate for more than 7 days. Actual in-house tests have shown results up to 5 times that amount.

#### **TECHNICAL DATA**

Physical Properties: Blended synthetic fibers and polyethylene film. Inert hot-melt adhesive.

Antimicrobial Protection	Yes
Weight12 lbs/rc	ll • 17.28 oz/sq yd • 1.92 oz/sq ft
Thickness	0.125"
Density	11.52 lbs / ft <sup>3</sup>
Compression Resistance @ 25%	9.5 psi
Compression Resistance @ 30%	16.6 psi
Compression Resistance @ 50%	85.5 psi
Breaking Strength	Length 72.1 lbs; Width 100 lbs
Compression Set @ 25%	18.8%
R-Value (@0.125")	0.58 hr-ft <sup>2</sup> -degF/Btu (4.64/ inch)

**Flammability** Meets or exceeds Federal Flammability Standard: 1-70 (Pill Test) and ASTM E84 Steiner Tunnel Test.

**Volatile Organic Compounds (VOC)** Tested for 81 different off-gas compounds in accordance with CA 01350. Passed to the level of Collaborative for High Performance Schools (CHPS) and Office Spaces.

**Product Emissions** Passed the most rigorous emissions test: Section 01350 for CHPS and Standard Office 8mm Laminate.

### **SOUND PROPERTIES**

# IMPACT SOUND TRANSMISSION

The method is designed to measure the impact sound transmission performance of a floor-ceiling assembly in a controlled laboratory environment.

IIC	Flooring	Sub-floor
71	Laminate	WITH ceiling assembly
57	Floating Engineered Wood	WITH ceiling assembly
68	Laminate	WITH/suspended gypsum board assembly
60 (Field IIC)	Laminate	NO ceiling assembly
55	Laminate	6" concrete slab with no ceiling assembly
59	Engineered Wood	Fire Rated System - UL L521 Wood frame with 3/4" gypsum concrete
61	Floating Engineered Hardwood	Wood frame, gypsum concrete, isolation clips
59	Floating Engineered Hardwood	Wood frame and gypsum concrete

### **SOUND TRANSMISSION LOSS**

The sound-insulating property of a partition element is expressed in terms of the sound transmission loss.

STC	Flooring	Sub-floor
66	Floating Engineered Wood	WITH suspended gypsum board assembly
54	Laminate	NO ceiling assembly
52	Laminate	Wood frame and gypsum concrete
50	Laminate	6" concrete slab with no ceiling assembly
61	Engineered Wood	Fire Rated System - UL L521 Wood frame with 3/4" gypsum concrete
59	Floating Engineered Hardwood	Wood frame, gypsum concrete, isolation clips
61	Floating Engineered Hardwood	Wood frame and gypsum concrete

#### **DELTA TEST**

Tests the impact insulation difference between a bare concrete subfloor with no flooring materials and the same concrete subfloor with flooring and underlayment.

Delta IIC	Flooring
24	QuietWalk Plus under Laminate







