SHORT-TERM RADON GAS TEST KIT

STEP 1: PREPARING FOR TEST
In order to provide valid results, the tests must be performed under **closed house conditions.** Close all windows and doors for at least 12 hours prior to testing and keep them closed except for normal entry and exit. **DO NOT OPERATE:** • Fans • Whole house fans • Fireplaces. **Note:** Installed permanent radon mitigation systems should be functioning during the testing period. Operate furnaces and central heating / air conditioning normally. Window air conditioning units should be operated with the vent closed or set in recycle mode during the testing. Do not conduct testing during severe weather conditions.

STEP 2: SELECT THE TEST AREA
Place the ***PRO-LAB®*** Radon Gas Detectors in the lowest livable level of your home away from drafts, vents, doors or windows. Do not place the detectors in the following areas: Kitchen, laundry room, closets, direct sunlight, or near any heat source.

STEP 3: STARTING TEST
Decide how many detectors you are going to use. Use one detector for screening purposes, use two detectors for real estate transactions.
Remove and save the cap(s) from the detector(s). Place the uncapped detector(s) on a flat surface at least two (2) feet above the floor and three (3) feet from any outside wall. The detector(s) should be placed six (6) inches from each other. Record the start date (MM/DD/YY) and exact time in hours and minutes (HH:MM), including AM/PM. Allow the Radon Gas Detector(s) to remain uncapped and undisturbed in the same location for at least 48 hours and no more than (96 hours). Note: If you leave detector(s) open for less than 48 hours or more than 96 hours the results will be invalid. You will need to buy another test kit and repeat the test. You may use one (1) detector as a blank sample, if you do simply leave one detector with its cap. Please mark the detector as a blank in the data card.

STEP 4: ENDING TEST
After 48 - 96 hours replace the cap(s) on the detector(s) and make sure to record the end date (MM/DD/YY) and the exact time in hours and minutes (HH:MM), including AM/PM.
STEP 5: LAB RESULTS DIRECTIONS ■ Standard within 5 business days, $20 lab fee per detector.
■ Express in 3 business days, $30 lab fee per detector.
Place the Radon Gas Detector(s) within 24 hours of completing the test in the pre-paid postage envelope provided along with the completed test location form and the proper payment amount, money order, credit card payment (Visa, Mastercard, Discover, or AMEX only) or check (made payable to ***PRO-LAB®***). If you opt to use Express Lab Results you must send your sample to ***PRO-LAB®*** using an overnight shipping company such as Federal Express or UPS. Send the test kit to ***PRO-LAB®*** 1675 N. Commerce Parkway, Weston, FL 33326. (Express samples can only be received Monday – Friday). Email/text notifications will let you know when your sample is received. You may print and view your results on the **PROLAB Test Kits** app or at **prolabinc.com/results.**

***Special Note: New Jersey residents must add an additional $10 fee per detector - made payable to *PRO-LAB®*. *PRO-LAB®* is required to pay an Administrative Fee to the NJDEP for Radon Tests conducted in New Jersey.**

For questions or more information go to prolabinc.com or call (954) 384-4446

Cut along dotted line

MUST BE RETURNED TO *PRO-LAB®*
TEST LOCATION AND PAYMENT FORM
COMPLETE INFORMATION REQUIRED

Name:
Test Address:
City: State:
County: Zip:
Municipality:
Phone: – –

EMAIL ADDRESS REQUIRED FOR RESULTS
Email:

Radon Detector Serial Number # **#**

REQUIRED (Start) Cap Removed: Date M M / D D / Y Y **Exact Start Time:** H H : M M **AM/PM**

REQUIRED (End) Cap Replaced: Date M M / D D / Y Y **Exact End Time:** H H : M M **AM/PM**

Test Purpose: ❒ Real estate transaction ❒ Initial screening ❒ Follow-up test ❒ Pre-mitigation ❒ Post mitigation ❒ Other _____

Building Type: ❒ Residential ❒ Non Residential ❒ Single Family Home ❒ Condo ❒ Townhouse ❒ Apartment ❒ Day Care ❒ Day Care in Public School ❒ Other _____
❒ School School Code:

Structure Type: ❒ Basement ❒ Crawl space ❒ Slab on Grade ❒ Other _____

Floor Tested: ❒ Basement ❒ 1st Floor ❒ 2nd Floor Name of room tested _____

Closed building conditions were maintained during the test?: ❒ Yes ❒ No

Do you have a Radon Mitigation system installed?: ❒ Yes ❒ No

Is vial B a blank sample?: ❒ Yes ❒ No

***Must be received within 7 (business days) in order to be processed.**

STANDARD LAB RESULTS
❒ **$20 (1 sample)** ❒ **$30** *(NJ Residents)*
❒ **$40 (2 samples)** ❒ **$60** *(NJ Residents)*

EXPRESS RADON LAB RESULTS
❒ **$30 (1 sample)** ❒ **$40** *(NJ Residents)*
❒ **$60 (2 samples)** ❒ **$80** *(NJ Residents)*

MAKE CHECKS PAYABLE TO ***PRO-LAB®*** ❒ CHECK # ❒ MONEY ORDER

CREDIT CARD: ❒ Visa ❒ Mastercard ❒ Discover ❒ AMEX
Credit Card #: Exp. Date: /

CC SECURITY CODE (3 or 4 digits):
Name on Card / Check:
Street Address: Zip:
City: State:
Signature: Date: /

By submitting your sample to *PRO-LAB®* for analysis, you authorize *PRO-LAB®* and/or its affiliate representatives to contact you regarding your results.
Al enviar su prueba a PRO-LAB® para su análisis, usted autoriza a PRO-LAB® y / o a sus representantes afiliados para que se comuniquen con usted con respecto a sus resultados.

PRO-LAB® **• 1675 N. COMMERCE PARKWAY • WESTON • FL 33326**
MUST BE RETURNED WITH YOUR SAMPLE TO *PRO-LAB®*

RA100